

**Make sure, that the following items are included:**

- radon detector(s) in a sealed bag
- fillable form for each detector
- return envelope(s)

If any of these items are missing or the detector has been opened, please contact Radiation and Nuclear Safety Authority on Tuesdays 10am–1pm tel. (09) 7598 8497 (the telephone service is closed from Midsummer to the end of July and in weeks 51-52).


**Starting the measurement:**


- please start the measurement as soon as possible after you have received the detectors
- **remove the detectors from the plastic bag**, but do not open the detectors
- mark the measurement **starting date** and other information on the **form** or through **STUK e-service**


**Place the detector:**


- measurement point needs to be close to a workspace or in the working area
- place the detector at breathing height of the workers (the position of the detector does not affect the results)

**Do not place the detector:**

- near a door, window or an air vent (minimum distance 1,5 m)
- less than 25 cm from a concrete or stone surface or from a lightweight brick wall
- in wet spaces or on the floor (minimum distance 1 m)
- in a location where there is heat or steam


**Ending the measurement:**

- mark the measurement ending date on the form or through STUK e-service
- send the detectors and the form to STUK using the return envelope **immediately after ending the measurement**
- one return envelope can hold 3-4 detectors with their forms
- if you send the measurement dates and other information through e-service, you don't need to return the forms
- return all of the measurement sites detectors and their corresponding forms in the same shipment
- **remember to pay for the postal fee of the return envelope, so that the detectors arrive at STUK**
- the detectors can also be returned to STUK by regular letter or parcel, in which case the recipient of the shipment can be written as "Radiation and Nuclear Safety Authority, Radon laboratory, Jokiniemenkuja 1, 01370 Vantaa" (tel. +358 50 476 3978, email. radonlaboratorio@stuk.fi)
- the results will be sent to the customer in about one month after STUK has received the detectors


**NOTE!**

- The recommend length of the measurement is 3 months between 1.9.-31.5. The length of the measurement must be at least 2 months.
- STUK's Natural Radiation Regulation does not accept measurements made outside of the measurement season.

